

PERFORMANCE RESULTS

Klargester NUF
Gjerdrumsvei 10 D
0484 Oslo
Norway



EN 12566-3

Small wastewater Treatment systems for up to 50 PT- Part 3

BioDisc (BA) with chemical dosing equipment (5 PT with 200 litres per person per day)

Hydraulic Daily Load	1.00 m ³ /day
Material	Glass Reinforced Plastic. (GRP)
Water tightness (water test)	Pass
Nominal flow Treatment Efficiency	COD 87%
	BOD ₅ 93%
	SS 90%
	NH ⁴ 63%
	P 90%
	N Total 49%
pH	7.2
Electrical Consumption	1.36kWh/day

Performance tested by;

Date tests completed November 2006

Prüfinstitut für Abwassertechnik
(PIA GmbH)
Hergenrather Weg 30
D-52074 Aachen
Germany

PIA GmbH
Prüfinstitut für Abwassertechnik
Hergenrather Weg
52074 Aachen

